

PlayPower LT Farmington

PlayPower LT Farmington, Inc.
 In care of Boyce Recreation
 PO Box 734155
 Dallas, TX 75373-4155 US
 (616) 499-7400
 office@boycerec.com



Estimate

ADDRESS	SHIP TO	ESTIMATE	4101	
Frantz Volcy City of Englewood 2-10 North Van Brunt Street Englewood, NJ 07631 USA	Frantz Volcy City of Englewood Williams St Park Englewood, NJ 07631 USA	EXPIRATION	01/21/2024	
REP NAME		DATE		
ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
Equipment - Tikes	LITTLE TIKES "UNLIMITED PLAY PLATINUM LEVEL" FULLY INCLUSIVE PLAYGROUND PER DRAWINGS <ul style="list-style-type: none"> - Unlimited Play Platinum Level play structure ages 5-12 playground. All deck levels can be reach via ADA ramp access. - Unlimited Play Platinum Level play structure ages 2-12 playground. All deck levels can be reach via ADA ramp access. - 8 Bay Swings: <ul style="list-style-type: none"> - 2 Inclusive seats ages 2-12 - 2 Generation seats ages 2-12 (mommy and me) - 2 Tot seats ages 2-5 - 2 Belt seats ages 5-12 - NRG Web Hammock - Turnabout Unlimited Play Spinner (inclusive play ages 2-12) - Quiet Grove (inclusive play ages 2-12) - Concerto Inclusive musical instruments ages 2-12 - Unlimited Play Simon Says Panel (inclusive play ages 2-12) - Unlimited Play Silly Face Panel (inclusive play ages 2-12) - (8) 6' Recycled Plastic Benches with concrete pads - (2) Receptacles: Trash & Recycle 	1	297,022.47	297,022.47
Freight	LITTLE TIKES FREIGHT - 2 dedicated truckloads	1	10,974.96	10,974.96
Installation	INSTALLATION PER DRAWINGS <ul style="list-style-type: none"> - Remove & dispose of old playground - Install playground per drawings and specs - Install site amenities - Site prep and 420 linear feet of curbing for safety surfacing - Playground entrance ADA walkway 	1	172,500.00	172,500.00

Surfacing - PIP	PRO-TECHS POURED IN PLACE SAFETY SURFACING - 9,504sf total - Use zone 144' x 66' - 3.5" thickness - 8' fall height	9,504	22.03	209,373.12
Surfacing - PIP	STONE BASE FOR POURED IN PLACE SURFACING - 9,504sf total - 4' depth - Delivered & installed	9,504	3.30	31,363.20

SUBTOTAL	721,233.75
TAX	0.00
TOTAL	\$721,233.75

Accepted By

Accepted Date